


FORM PTO-1390 (REV 5-93)		U.S. DEPARTMENT OF COMMERCE PATENT AND TRADEMARK OFFICE	
TRANSMITTAL LETTER TO THE UNITED STATES DESIGNATED/ELECTED OFFICE (DO/EO/US) CONCERNING A FILING UNDER 35 U.S.C. 371		ATTORNEY DOCKET NO. 100341-00009	
		DATE: June 4, 2001	
		U.S. APPLN. NO. (IF KNOWN, SEE 37 C.F.R. 1.5) Not Yet Assigned <b>097856178</b>	
INTERNATIONAL APPLICATION NO. PCT/JP00/06872	INTERNATIONAL FILING DATE 2 October 2000	PRIORITY DATE CLAIMED 4 October 1999	
TITLE OF INVENTION: FISHING GAME DEVICE			
APPLICANT(S) FOR DO/EO/US: Hiromu UESHIMA (Shiga, Japan); Katsuya NAKAGAWA			
<ol style="list-style-type: none"> <li>1. <input checked="" type="checkbox"/> This is a <b>FIRST</b> submission of items concerning a filing under 35 U.S.C. 371. (THE BASIC FILING FEE IS ATTACHED)</li> <li>2. <input type="checkbox"/> This is a <b>SECOND</b> or <b>SUBSEQUENT</b> submission of items concerning a filing under 35 U.S.C. 371.</li> <li>3. <input checked="" type="checkbox"/> This express request to begin national examination procedures [35 U.S.C. 371(f)] at any time rather than delay examination until the expiration of the applicable time limit set in 35 U.S.C. 371(b) and PCT Articles 22 and 39(1).           <ul style="list-style-type: none"> <li><input type="checkbox"/> A proper demand for International Preliminary Amendment was made by the 19th month from the earliest claimed priority date.</li> <li><input checked="" type="checkbox"/> A copy of the International Application as filed [35 U.S.C. 371(c)(2)]               <ol style="list-style-type: none"> <li>a. <input checked="" type="checkbox"/> is transmitted herewith (required only if not transmitted by the International Bureau).</li> <li>b. <input type="checkbox"/> has been transmitted by the International Bureau.</li> <li>c. <input type="checkbox"/> is not required, as the application was filed in the United States Receiving Office (RO/US).</li> </ol> </li> <li><input checked="" type="checkbox"/> A translation of the International Application into English [35 U.S.C. 371(c)(2)].</li> <li><input checked="" type="checkbox"/> Amendments to the claims of the International Application under PCT Article 19 [35 U.S.C. 371(c)(3)]               <ol style="list-style-type: none"> <li>a. <input type="checkbox"/> are transmitted herewith (required only if not transmitted by the International Bureau).</li> <li>b. <input type="checkbox"/> have been transmitted by the International Bureau.</li> <li>c. <input type="checkbox"/> have not been made; however, the time limit for making such amendments has NOT expired.</li> <li>d. <input checked="" type="checkbox"/> have not been made and will not be made.</li> </ol> </li> <li><input type="checkbox"/> A translation of the amendments to the claims under PCT Article 19 [35 U.S.C. 371(c)(3)].</li> <li><input checked="" type="checkbox"/> An oath or declaration of the inventor(s) [35 U.S.C. 371(c)(4)].</li> </ul> </li> <li>10. <input type="checkbox"/> A translation of the annexes to the International Preliminary Examination Report under PCT Article 36 [35 U.S.C. 371(c)(5)].</li> </ol> <p>Items 11 - 16 below concern other document(s) or information included:</p> <ol style="list-style-type: none"> <li>11. <input checked="" type="checkbox"/> An Information Disclosure Statement under 37 C.F.R. 1.97 and 1.98.</li> <li>12. <input checked="" type="checkbox"/> An assignment document for recording. A separate cover sheet in compliance with 37 C.F.R. 3.28 and 3.31 is included.</li> <li>13. <input checked="" type="checkbox"/> A FIRST preliminary amendment. <input type="checkbox"/> A SECOND or SUBSEQUENT preliminary amendment.</li> <li>14. <input type="checkbox"/> A substitute specification.</li> <li>15. <input type="checkbox"/> A change of power of attorney and/or address letter.</li> <li>16. <input checked="" type="checkbox"/> Other items or information: PCT/ISA/210 International Search Report (in Japanese); International Publication Gazette WO 01/24898 (in Japanese); copy of the originally filed petition; Declaration of the Translation of International Application No. PCT/JP00/06872 Drawings (6 sheets)</li> </ol>			


U.S. APPL. NO. (IF KNOWN) SEE 37 C.F.R. 1.50 Not Yet Assigned <div style="font-size: 2em; font-weight: bold; margin-top: 10px;">09/856178</div>	INTERNATIONAL APPLICATION NO. PCT/JP00/06872	ATTORNEY DOCKET NO. 100341-00009 DATE: June 4, 2001					
17. <input checked="" type="checkbox"/> The following fees are submitted: <b>Basic National Fee [37 C.F.R. 1.492(a)(1)-(5)]:</b> Search Report has been prepared by the EPO or JPO.....\$860.00 International preliminary examination fee paid to USPTO (37 C.F.R. 1.482).....\$690.00 No international preliminary examination fee paid to USPTO (37 C.F.R. 1.482) but international search fee paid to USPTO [37 C.F.R. 1.445(a)(2)].....\$710.00 Neither international preliminary examination fee (37 C.F.R. 1.482) or international search fee [37 C.F.R. 1.445(a)(2)] paid to USPTO.....\$1,000.00 International preliminary examination fee paid to USPTO (37 C.F.R. 1.482) and all claims satisfied provisions of PCT Article 33(2)-(4).....\$ 100.00		<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th style="width: 50%;">CALCULATIONS</th> <th style="width: 50%;">PTO USE ONLY</th> </tr> <tr> <td style="height: 100px;"></td> <td></td> </tr> </table>		CALCULATIONS	PTO USE ONLY		
CALCULATIONS	PTO USE ONLY						
<b>ENTER APPROPRIATE BASIC FEE AMOUNT =</b>		\$ 860.00					
Surcharge of \$130.00 for furnishing the oath or declaration later than <input type="checkbox"/> 20 <input type="checkbox"/> 30 months from the earliest claimed priority date [37 C.F.R. 1.492(e)].		\$ 0.00					
Claims	Number Filed	Number Extra	Rate				
Total Claims	7 - 20 =	0	X \$ 18.00				
Independent Claims	1 - 3 =	0	X \$ 80.00				
Multiple dependent claim(s) (if applicable)		+ \$270.00	\$ 270.00				
<b>TOTAL OF ABOVE CALCULATIONS =</b>		\$ 1,130.00					
Reduction by one-half for filing by small entity, if applicable. Verified Small Entity statement must also be filed. (Note 37 C.F.R. 1.9, 1.27, 1.28).		\$ 565.00					
<b>SUBTOTAL =</b>		\$ 565.00					
Processing fee of \$130.00 for furnishing the English translation later the <input type="checkbox"/> 20 <input type="checkbox"/> 30 months from the earliest claimed priority date [37 C.F.R. 1.492(f)].		\$ 0.00					
<b>TOTAL NATIONAL FEE =</b>		\$ 565.00					
Fee for recording the enclosed assignment [37 C.F.R. 1.21(h)]. The assignment must be accompanied by an appropriate cover sheet (37 C.F.R. 3.28, 3.31). \$40.00 per property		\$ 40.00					
<b>TOTAL FEES ENCLOSED =</b>		\$ 605.00					
		Amount to be refunded	\$				
		Charged	\$				
a. <input type="checkbox"/> A check in the amount of \$            to cover the above fees is enclosed. b. <input checked="" type="checkbox"/> Please charge my Deposit Account No. 01-2300 in the amount of \$605.00 to cover the above fee. A duplicate copy of this sheet is enclosed. c. <input checked="" type="checkbox"/> The Commissioner is hereby authorized to charge any additional fees which may be required, or credit any overpayment to Deposit Account No. 01-2300.							
NOTE: Where an appropriate time limit under 37 C.F.R. 1.494 or 1.495 has not been met, a petition to revive [37 C.F.R. 1.137(a) or (b)] must be filed and granted to restore the application to pending status.							
SEND ALL CORRESPONDENCE TO: <b>Arent Fox Kintner Plotkin &amp; Kahn</b> <b>1050 Connecticut Avenue, N.W.</b> <b>Suite 600</b> <b>Washington, D.C. 20036-5339</b> <b>Tel: (202) 857-6000 Fax: (202) 638-4810</b>							
		 Charles M. Marmelstein Reg. No. 25,895					

## DECLARATION

I, Yoshito Yamada, c/o YAMADA PATENT OFFICE of The Tanabe Bldg., 6-6, Fushimimachi 2-chome, Chuo-ku, OSAKA, Japan, declare that I am the translator of the documents attached, which are to the best my knowledge and belief a true and correct translation of International Application No. **PCT/JP00/06872**.

DATE: May 29, 2001

Signature of translator

  
Yoshito Yamada

09/856178

JG08 Rec'd PCT/PTO 04 JUN 2007

**PATENT APPLICATION**

IN THE UNITED STATES PATENT AND TRADEMARK OFFICE

In re the Application of:

Hiromu UESHIMA et al.

Application No.: Not Yet Assigned

Filed: currently herewith

Attorney Dkt. No.: 100341-00009

For: FISHING GAME DEVICE

**PRELIMINARY AMENDMENT**

Commissioner for Patents  
Washington, D.C. 20231

Date: June 4, 2001

Sir:

Prior to initial examination of the application, please amend the above-identified application as follows:

**IN THE CLAIMS:**

Please amend claims 4-5 as follows:

4. (Amended) A fishing game apparatus according to claim 1, further comprising an AV cable connecting said casting rod with said television monitor to supply a video signal and audio signal from said game processor to said television monitor through said AV cable.

5. (Amended) A fishing game apparatus according to claim 1, further comprising

an information storage medium,


said game processor including at least operation processing means, image processing means and a memory.

### REMARKS

Claims 1-6 are pending in this application. By this Amendment, claims 4-5 are amended to delete multiple dependency. No new matter is contained in the amendments.

Please charge any fee deficiency or credit any overpayment to Deposit Account No. 01-2300.

Respectfully submitted,



Charles M. Marmelstein  
Registration No. 25,895

ARENT FOX KINTNER PLOTKIN & KAHN, PLLC  
1050 Connecticut Avenue, N.W.,  
Suite 600  
Washington, D.C. 20036-5339  
Tel: (202) 857-6000  
Fax: (202) 638-4810

Attachment: Amended Claims Marked Up to Show Amendments

### Amended Claims Marked Up to Show Amendments

4. (Amended) A fishing game apparatus according to [any claims of 1 to 3] claim 1, further comprising an AV cable connecting said casting rod with said television monitor to supply a video signal and audio signal from said game processor to said television monitor through said AV cable.

5. (Amended) A fishing game apparatus according to [any claims of 1 to 4] claim 1, further comprising  
an information storage medium,  
said game processor including at least operation processing means, image processing means and a memory.

**SPECIFICATION****Fishing Game Device****TECHNICAL FIELD**

5 This invention relates to a fishing game apparatus and, more particularly, to a novel game apparatus having a casting rod to be electrically connected to a television monitor to allow casting with the casting rod, thereby playing a fish game on the game screen.

**PRIOR ART**

10 Conventionally, fishing games has been popular in video game. Playing a fishing game on a television is costly because of a need to prepare a video game console and fishing game software. With a controller attached to the video game console, there is short of a sense of reality. Hence, nowadays the controllers dedicated for fishing games have bee available in the market. The use of such an exclusive controller pushes the costs up.

15 On the other hand, fishing game apparatus of a casting rod shape is also available. This fishing game apparatus has, in a casting rod, an acceleration switch built-in, the game processor and a liquid crystal display. A casting action in an actual manner gives an acceleration to the rod. If the magnitude of the acceleration is greater than a certain value, the acceleration switch turns on. The game processor detects the timing when the acceleration switch turns on. On the basis of the timing, the game processor determines kind and size of available fishes by making reference to a data table, thereby determining whether a fish is to be hooked up or not. The game player is allowed to watch a series of processes with displaying a fishing field or water place on the liquid crystal display.

20

25



In the latter conventional art, not a TV game, a game player needs not to prepare a costly video game apparatus, therefore the player can enjoy a fishing game readily. However, the LCD screen is too small to watch the game image, the fishing game still lacks reality.

5

## SUMMARY OF THE INVENTION

Therefore, it is a primary object of the present invention to provide a fishing game apparatus which displays a game scene on a television monitor to allow a fishing game to be played with such a realistic sensation as not to be offered by the conventional TV video game.

10

The present invention is a fishing game apparatus for displaying a game scene of a fishing game on a television display, the fishing game apparatus comprising: a casting rod; an acceleration sensor provided in the casting rod to output an acceleration signal during casting; and a game processor provided in the casting rod to determine a casting distance on the game screen by processing an acceleration signal.

15

The casting rod incorporating the acceleration sensor and game processor is connected to the television monitor through an AV cable, etc. When a game player does casting action using the casting rod (casting) toward the monitor screen, the game processor calculates a casting distance in accordance with an acceleration signal from the acceleration sensor, and displays on the screen a splashdown point in a position according to the distance.

20

Incidentally, in the case the casting rod has a function of a light gun, the game processor calculates a position of a light spot on the television monitor according to an output from light spot detecting means and displays a rod on the game screen as if a line is casted in the direction of the light spot.

25

According to the invention, a fishing game can be readily enjoyed because of unnecessary of preparing a video game console or game software. Displaying a game image on a television monitor allows a game player to have more realistic sensation than that of the conventional liquid crystal display.

5 Further, it is possible to detect a casting intensity, or casting distance, according to an acceleration signal sent from an acceleration sensor. Thus, reality is further enhanced.

The above described objects and other objects, features, aspects and advantages of the present invention will become more apparent from the following detailed description of the present invention when taken in conjunction with the accompanying drawing.

#### 10 BRIEF DESCRIPTION OF THE DRAWINGS

Figure1 is a configuration diagram showing a fishing game apparatus of an embodiment of the present invention;

15 Figure 2 is an illustrative view showing an example of a game screen in the Figure1 embodiment;

Figure 3 is an illustrative view showing a structure of a casting rod of the Figure1 embodiment;

Figure 4 is a block diagram showing the Figure1 embodiment;

20 Figure 5 is a circuit diagram showing an example of an acceleration sensor of the Figure1 embodiment; and

Figure 6 is a flowchart showing operation of the Figure1 embodiment.

#### BEST MODE FOR CARRYING OUT THE INVENTION

25 A fishing game apparatus 10 of an embodiment of the present invention as illustrated in Figure 1 includes a casting rod 12. The rod 12 is connected to an AV

terminal 14 of a television monitor 16 through an AV cable 18. When a game player does casting action using the casting rod 12 toward a screen of the television monitor 16, a rod a11 (Figure 2) casts a line on the game screen of the monitor 16. The television monitor 16 can use a display capable of displaying an image by a video signal for television  
5 monitor such as, raster scanning display and a dot matrix display. However, in the case a direction identifying function cooperative with the television monitor 16 is added, as hereinafter described, a raster scanning display must be used as the television monitor 16.

The casting rod 12 has a housing 30 (Figure 3) formed of plastic, or the like. The housing has, on the top surface, a power supply switch 20, a select key 22 and a tension  
10 key 24. The select key 22 on a menu screen is operated to select a lure kind and a fishing field (water place). The tension key 24 is used to adjust a tension of a fish line displayed on the game screen, and includes upward and downward keys for increasing and decreasing the tension.

A reel handle 26 is provided in a lower part of the housing of the casting rod 12  
15 which the game player is allowed to reel in order to hook a fish during fighting, or the like. The casting rod 12 has a relatively tough fish line 28 formed of plastic, or the like. The fish line 28 has one end fixedly held at tip of the casting rod 12, and the other end is elastically held at the lower part of the housing the reel handle is provided. When shaking the casting rod 12 for casting, the fish line 28 is drawn by a game player, thereby turning  
20 a casting switch 56 (Figure3) on.

In the fishing apparatus 10 of Figure 1, a game screen as illustrated in Figure 2 is displayed on the television monitor 16. The game screen is formed with a distant view display region, a fishing field display region and a game information indication region. The distant view display region is mainly a background picture image called “text  
25 screen”, and the fishing field display region is mainly a moving picture image called

“sprite”. Besides a change of a color to express a lapse of time, during a game, the distant view display region is not changed in each display element. The fishing field display region displays a water place where a rod figure (may be referred merely to as “rod”) a11, and a fishing line figure a12 extending from the tip end of the rod figure a11 to a splashdown point a13 are displayed. By shaking the casting rod 12 of Figure 1, the fishing field display region displays the splashdown point a13 that is determined by a direction of the casting rod 12 toward the screen 16, and an intensity of the shaking.

The game information indication region consists of a distance indication area a14 for indicating a casting distance on a meter unit, a weight indication area a15 for indicating a weight of a captured fish on a kilogram unit, and a tension indication area a16 for indicating a tension on the fishing line a12 with a bar graph step by step. Incidentally, in the embodiment, a tension exceeding a predetermined value, results in lost (failure of the fishing). Accordingly there is a need for a game player to control the tension with skilful operation.

As shown in Figure 3 the casting rod 12, as viewed from the sideways, for example, includes the gun shaped housing 30 having a battery box 34 housing a battery 32, thereby supplying electric power to each component. Incidentally, so-called an AC/DC adapter may be used in place of the battery. However, considering game player’s actual casting, a battery is more preferable because of an obstructive cord of the AC/DC adapter.

A boss 36 is formed extending vertically downward from an upper inside of the housing 30 in a position forward of the battery within the housing 30. The boss 36 holds a printed circuit board 38. The printed circuit board 38 has thereon keys 22 and 24. A game processor 70 shown in Figure 4 is also mounted on the printed board 38.

A boss 40, extending vertically downward alike the boss 36, is formed at a front

part in the housing 30. The boss 40 holds an acceleration sensor board 42. The acceleration sensor board 42 is mounted thereon with a piezoelectric buzzer 44 having a function as an acceleration sensor and circuit elements such as transistors used therewith. Herein, circuit elements on the acceleration sensor board 42 including the piezoelectric buzzer 44 are referred to as an acceleration sensor 46.

A tip rod 48, protruding forward and of plastic or the like, is attached in the front end of the housing 30.

A reel housing 50 is formed at the lower part of the housing 30. The reel housing 50 is a part of the housing 30 but may be shown at another reference numeral, for the sake of convenience. Above-mentioned fish line 28 has one end fixed to the end of the tip rod 48 and the other end extended to the inside the reel housing 50. The other end of the fish line 28 is fixed through a spring 52 within the reel housing 50. Accordingly, when the fish line 28 is drawn by the game player, the spring 52 is extended to move the fish line 28 so that the other end of the fish line 28 is drawn out from the reel housing 50.

Accordingly, an action chip 54 fixed at the other side of the fish line 28 is rotated, thereby turning the casting switch 56 on. The action chip 54 is rotatably held at an inner wall of the reel housing 50 and fixed at a free end to the fish line 28. Consequently, when the fish line 28 is drawn out, the action chip 54 correspondingly rotates in the direction of drawn. The action chip 54 presses a contact, thereby turning a casting switch 56 on.

A tip-opened cylindrical part 58 is formed in a front part of the reel housing 50. In the vicinity of the tip opening of the cylindrical part 58, a focusing lens 60 formed of plastic or the like is attached. In the cylindrical part 58 at a rear of the focusing lens 60, a light-receiving element, e.g. the phototransistor 62 is provided in a position of receiving the light focused by the focusing lens 60. Consequently, when the light is incident through a focusing lens 60, the phototransistor 62 receives the light and outputs an

electrical signal. The signal from the phototransistor 62 is inputted to after-mentioned game processor 70 (Figure4), whereby the game processor 70 (Figure 4) can recognize where the casting rod 12 is directed on the screen. That is, the focusing lens 60 and the phototransistor 62 serves as so called a light pen or a light gun to detect the position of a light spot during rasterscanning the television monitor 16.

As shown in Figure 1, the reel handle 26 is rotatably held to the reel housing 50. A slit plate 64 fixed on a rotating shaft of the reel handle 26 is rotatably supported within the reel housing 50. The slit plate 64 has a plurality of slits distributed at an equal interval in the circumferential direction. A photo-interrupter 66 has a light-emitting element and a light-receiving element oppositely disposed sandwiching the slit plate 64. Accordingly, as the slit plate 64, i.e. reel handle 26 (Figure1) rotates, a pulse signal is outputted from the photo-interrupter 66. The pulse signal is inputted to hereinafter-mentioned game processor 70. Due to this, the game processor 70 can detect a rotation amount of the reel handle 26.

A vibrator 68 such as an eccentric motor is further provided within the reel housing 50. The vibrator 68 operates, upon hooking a fish, to give vibrations to the player, as if he or she actually played fishing. The vibrator 68 can use, besides an eccentric motor, anything such as an electromagnetic solenoid, provided that it offers this kind of vibration.

The game processor 70 shown in Figure 4 is mounted on the printed circuit board 38 shown in Figure 3. The game processor 70 may use any processor. However, the embodiment uses a high-speed processor that the present applicant has developed and filed. For example, the high-speed processor is disclosed in detail in a Japanese Patent Laid-open No. 307790/1998 (G06F13/36, 15/78) and the corresponding U.S. Pat. Application No. 09/019,277.

The game processor 70, although not shown, includes various processors such as an CPU, a graphic processor, a sound processor and a DMA processor, and includes an A/D converter for receiving an analog signal and an input /output control circuit for receiving an inputted signal such as a key operation signal and supplying an output signal to an external apparatus. The CPU executes required operation according to an inputted signal and provides a result thereof to another processor. The graphic processor executes a graphic process as required by the operation result, and generates a changing game image. Similarly, the sound processor executes a sound process required by the operation result.

The game processor 70 is connected with an external memory 72 through an external bus. The external memory 72 is ROM and/or RAM, and includes a program area 72a, a data table area 72b, an image data area 72c, and a sound data area 72d. The program area 72a is stored with a game control program shown in Figure 6, hereinafter referred. The data table area 72b is stored with a data table showing weather, kind of fish according to the weather, fish inhabitation, and fish weight for each water place (water field). The image data area 72c is stored with all the image data such as the rod figure a11 and the fishing line figure a12 displayed on the game screen shown in Figure 2, and other required image data. The sound data area 72d is stored with sound for game music and effective sound.

Then, while the output from the phototransistor 62 explained referring to Figure 3 is inputted to the game processor 70, an acceleration correlation voltage signal from the acceleration sensor 46 is provided to an A/D converter input of the game processor 70. The pulse signal from the photo-interrupter 66 is provided to a mouse input of the game processor 70. A signal from each of keys or switches 22, 24 and 56 is inputted to an input port of the game processor 70. Meanwhile, the game processor 70 outputs through an

output-port a drive signal to the vibrator 68.

Then, a video signal (forming game images) and audio signal (sound effect, music) is provided from the game processor 70 to the television monitor 16 through the AV cable 18.

5 Explanation is herein made on the utilization of the piezoelectric buzzer 44 as an acceleration sensor. As well known, the piezoelectric buzzer 44, as shown in Figure 5, has a piezoelectric ceramic plate 44a such as of barium titanate or PZT having electrodes 44b, 44c formed on the main surfaces. In the embodiment, the piezoelectric buzzer 44 is utilized as an acceleration sensor.

10 More specifically, as described above, when swinging the casting rod 12, the piezoelectric buzzer 44 is provided within the casting rod 12 such that the main surface thereof is perpendicular to a direction of swinging the casting rod 12. When the casting rod 12 is swung by the game player, an intense centrifugal force acts thereon. Accordingly, the piezoelectric plate 44a of the piezoelectric buzzer 44 is distorted by the  
15 centrifugal force to cause a potential difference between the main surfaces of the piezoelectric plate 44a depending on the centrifugal force. The potential difference varies depending on the stress (centrifugal force) acted on the piezoelectric plate 44a. As the stress increases, the potential difference increases, while the stress is decreases, the potential difference decreases. In other words, the potential difference on the  
20 piezoelectric buzzer 44 varies in accordance with a velocity and intensity of swing of the casting rod 12 by the game player. Thus, this embodiment can use the piezoelectric buzzer 44 as an acceleration sensor.

The potential difference caused in the piezoelectric buzzer 44 is provided to a base of a transistor 45. Accordingly, the transistor 45 amplifies a magnitude of the potential  
25 difference, and outputs a voltage signal. The voltage signal is given an acceleration



correlation signal, and is inputted to the A/D converter of the game processor 70, as described above. Therefore, the game processor 70 can import the acceleration of the casting rod 12 as data during casting.

5 In the game mode, the game processor 70 controls the overall operation, according to the flowchart of Figure 6. Before starting the operation of Figure 6, a game player determines, on a menu screen, a fishing place, lure to be used, etc. in advance by utilizing the select key 22. First, in step S 1, the fish line 28 (Figure 1, Figure 3) is drawn out. Then turn the casting switch 56 on. Next, the game player swings the casting rod 12 in a feeling of actual fishing. At this time, the direction of casting is found by the light gun function mentioned above. In short, when the phototransistor 62 detects a rasterscanning light spot on television monitor 16, the game processor 70 detects the position of the light spot in the screen by making reference to horizontal and vertical counters (both not shown) counting a horizontal synchronizing signal and a vertical synchronizing signal, respectively. The position in the screen gives a direction of swinging the casting rod 12. 10 At the same time, because an acceleration signal from the acceleration sensor 46 is inputted to the game processor 70, the game processor 70 recognizes an acceleration, i.e. intensity of the swing occurring on the casting rod 12. In accordance with the casting direction and intensity (distance) thus detected, the game processor 70 determines positions and shapes of the rod figure a11, fishing line figure a12 and splashdown point a13 on the game screen as shown in Figure 2, and forms a corresponding game image. 15 20 Each process so far is executed in step S1.

Incidentally, the game processor 70 displays a numeral in a distance indication area a14 (Figure 2) according to the casting distance calculated in step S1.

25 In step S2, the process is executed according to an operation of the reel handle 26 by the game player. Namely, a length of the fish line a12 is detected on the basis of the

position of the rod a11 and the splashdown point a13 (lure position) on a game image screen. On the other hand, a length of reeling is calculated in real time by counting a pulse signal outputted from the photo-interrupter 66, upon rotation of the reel handle 26. By subtracting a length of reeling from a length of a fish line, a fish line at that time is  
5 calculated. Once a length of a fish line comes below a certain value in step S3, the end of reeling is determined. If there is no change until "Yes" is determined in step S3, the game player returns to step S1 to start again casting.

If "NO" is determined in step S3, that is, if there is a fish biting by the end of the reeling, the process proceeds to step S4. Then, whether a fish bites a lure or not is  
10 determined at random on the basis of the data table described above. If "YES" is determined in step S4, the game processor 70 outputs a drive signal to drive the vibrator 68 and give vibrations to player.

In step S5 and step S6, a hooking process is executed. The game processor 70 detects an intensity of hooking by utilizing the acceleration sensor 46 also this time.  
15 Then, in step S6, the game processor 70 determines on the basis of fish kind, lure kind, fish size, time between a biting and a hooking and hooking intensity, whether hooking is successful or not. If the hooking is successful, a fighting process is executed in the following step S7 and S8.

In step S7, the game player performs a fighting operation, such as controlling a  
20 tension of the fish line a12 (Figure 2) by utilizing the tension key 24 (Figure1, Figure4) during reeling, and changing a position of the rod a11 (Figure 2) up, down, left and right by swinging the casting rod 12. Then, the game processor 70 determines whether lost or not, according to the fact that tension reached a certain value or a fish moved outside a certain range or the like.

25 "NO" determination in step S8 means successful hooking. In step S9, the game

processor 70 executes the weight indication a15 (Figure 2) by reading data from a data table.

Meanwhile in step S1 to step S9 in Figure 6, the game processor 70 displays a tension changing in real time in the tension graph a16.

Although the present invention has been described and illustrated in detail, it is clearly understood that the same is by way of illustration and example only and is not to be taken bay way of limitation, the spirit and scope of the present invention being limited only by the terms of the appended claims.

## CLAIMS

1. A fishing game apparatus for displaying on a television monitor a game screen of a fishing game, the fishing game apparatus comprising:

a casting rod;

5 an acceleration sensor provided in said casting rod to output an acceleration signal during casting; and

a game processor provided in said casting rod to determine a casting distance on the game screen by processing the acceleration signal.

10 2. A fishing game apparatus according to claim 1, wherein said television monitor includes a scanning display, said casing rod further includes light spot detecting means for detecting a light spot of said scanning display, and said game processor determines a direction of casting on the game screen according to an output of said light spot detecting means.

15 3. A fishing game apparatus according to claim 1 or 2, wherein said acceleration sensor includes a piezoelectric buzzer element, and signal outputting means for outputting an acceleration signal on the basis of an acceleration correlation electric signal generated to said piezoelectric buzzer when said acceleration sensor is moved.

20 4. A fishing game apparatus according to any claims of 1 to 3, further comprising an AV cable connecting said casting rod with said television monitor to supply a video signal and audio signal from said game processor to said television monitor through said AV cable.

5. A fishing game apparatus according to any claims of 1 to 4, further comprising an information storage medium,

25 said game processor including at least operation processing means, image processing means and a memory,

said operation processing means executing a program code stored in said information storage medium and calculating the casting distance on the basis of said acceleration signal from said acceleration sensor to administer the fishing game,

5        said image processing means generating image information to be displayed on said television monitor by using image data stored in said information storage medium under control of said operation processing means,

said memory being for at least said operation processing means to hold progress and result of the operation.

10        6. A fishing game apparatus according to claim 5, wherein said information storage medium includes a non-volatile semiconductor memory.

## ABSTRACT

A fishing game apparatus (10) has a casting rod (12) connected to a television monitor (16). The casting rod (12) is built therein with a game processor and an acceleration sensor. During casting, an acceleration signal is inputted from the acceleration sensor to the game processor. The game processor calculates a corresponding casting distance and displays, on a game screen of the monitor (16), a splashdown point according to a distance calculated. By providing a light gun in the casting rod (12), the game processor can recognize a direction of casting and move the rod in that direction on the game screen.

FIG. 1




FIG. 2






FIG. 3




FIG. 4




FIG. 5





FIG. 6



**PATENT**

Attorney's Docket No. \_\_\_\_\_

Applicant or Patentee: SSD Company Limited

Serial or Patent No.: \_\_\_\_\_

Filed or Issued: \_\_\_\_\_

For: FISHING GAME DEVICE

**VERIFIED STATEMENT (DECLARATION) CLAIMING SMALL ENTITY  
STATUS (37 CFR 1.9(f) and 1.27(c))--SMALL BUSINESS CONCERN**

I hereby declare that I am

☐ the owner of the small business concern identified below:

☒ an official of the small business concern empowered to act on behalf of the concern

identified below:

NAME OF CONCERN SSD Comapny Limited

ADDRESS OF CONCERN 3-3-4, Higashiyagura, Kusatsu-shi, Shiga 525-0054, Japan

I hereby declare that the above identified small business concern qualifies as a small business concern as defined in 13 CFR 121.3-18, and reproduced in 37 CFR 1.9(d), for purposes of paying reduced fees under Section 41(a) and (b) of Title 35, United States Code, in that the number of employees of the concern, including those of its affiliates, does not exceed 500 persons. For purposes of this statement, (1) the number of employees of the business concern is the average over the previous fiscal year of the concern of the persons employed on a full-time, part-time or temporary basis during each of the pay periods of the fiscal year, and (2) concerns are affiliates of each other when either, directly or indirectly, one concern controls or has the power to control the other, or a third-party or parties controls or has the power to control both.

I hereby declare that rights under contract or law have been conveyed, to and remain with the small business concern identified above with regard to the invention, entitled:

FISHING GAME DEVICE

by inventor(s) Hiromu UESHIMA, Katsuya NAKAGAWA

described in:

- ☒ the specification filed herewith.  
☐ application serial no. \_\_\_\_\_, filed \_\_\_\_\_.  
☐ patent no. \_\_\_\_\_, issued \_\_\_\_\_.

If the rights held by the above identified small business concern are not exclusive, each individual, concern or organization having rights in the invention is listed below\* and no rights to the invention are held by any person, other than the inventor, who would not qualify as an independent inventor under 35 CFR 1.9(c) if that person made the invention, or by any concern which would not qualify as a small business concern under 37 CFR 1.9(d) or a nonprofit organization under 37 CFR 1.9(e).

\*NOTE: Separate verified statements are required from each named person, concern or organization having rights to the invention averring to their status as small entities. (37 CFR 1.27).

NAME \_\_\_\_\_

ADDRESS \_\_\_\_\_

☐ INDIVIDUAL      ☐ SMALL BUSINESS CONCERN      ☐ NONPROFIT ORGANIZATION

NAME \_\_\_\_\_

ADDRESS \_\_\_\_\_

☐ INDIVIDUAL      ☐ SMALL BUSINESS CONCERN      ☐ NONPROFIT ORGANIZATION

I acknowledge the duty to file, in this application or patent, notification of any change in status resulting in loss of entitlement to small entity status prior to paying, or at the time of paying, the earliest of the issue fee or any maintenance fee due after the date on which status as a small business entity is no longer appropriate. (37 CFR 1.28(b)).


I hereby declare that all statements made herein of my own knowledge are true and that all statements made on information and belief are believed to be true; and further that these statements were made with knowledge that willful false statements and the like so made are punishable by fine or imprisonment, or both, under Section 1001 of Title 18 of the United States Code, and that such willful false statements may jeopardize the validity of the application, any patent issuing thereon, or any patent to which this verified statement is directed.

NAME OF PERSON SIGNING Katsuya NAKAGAWA

TITLE OF PERSON OTHER THAN OWNER President of SSD Company Limited

ADDRESS OF PERSON SIGNING c/o SSD Company Limited, 3-3-4, Higashiyagura,

Shiga 525-0054, Japan

SIGNATURE  Date 2001 May 27.

Docket No.

ARENT FOX KINTNER PLOTKIN & KAHN, PLLC

## Declaration For U.S. Patent Application

As a below named inventor, I hereby declare that:

My residence, post office address and citizenship are as stated below my name.

I believe I am the original, first and sole inventor (if only one name is listed below) or an original, first and joint inventor (if plural names are listed below) of the subject matter which is claimed and for which a patent is sought on the invention **entitled**

(Insert Title) FISHING GAME DEVICE

the specification of which is attached hereto unless the following box is checked:

☒ was filed on October 2, 2000 As PCT International Application  
Number PCT/JP00/06872 and was amended on \_\_\_\_\_  
**and/or** was filed on \_\_\_\_\_ As U.S. Patent Application  
Number \_\_\_\_\_ and was amended on \_\_\_\_\_

I hereby state that I have reviewed and understand the contents of the above-identified specification, including the claim(s), as amended by any amendment referred to above.

I acknowledge the duty to disclose information which is material to patentability as defined in 37 C.F.R. '1.56.

I hereby claim foreign priority benefits under 35 U.S.C. '119(a)-(d) or '365(b) of any foreign application(s) for patent or inventor's certificate, or '365(a) of any PCT International application which designated at least one country other than the United States, listed below and have also identified below any foreign application for patent or inventor's certificate or PCT International Application having a filing date before that of the application(s) for which priority is claimed:

(List prior foreign applications)	Patent Application No. 11-283235 (Number)	Japan (Country)	4 October 1999 (Day/Month/Year Filed)	Priority Claimed <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No
	(Number)	(Country)	(Day/Month/Year Filed)	<input type="checkbox"/> Yes <input type="checkbox"/> No
	(Number)	(Country)	(Day/Month/Year Filed)	<input type="checkbox"/> Yes <input type="checkbox"/> No

I hereby claim the benefit under 35 U.S.C. '119(e) of any United States provisional application(s) listed below.

(Application Number)	(Filing Date)
(Application Number)	(Filing Date)

☐ See attached list for additional prior foreign or provisional applications.

I hereby claim the benefit under 35 U.S.C. '120 of any United States application(s) or '365(c) of any PCT International application(s) designating the United States of America listed below and, insofar as the subject matter of each of the claims of this application is not disclosed in the prior application(s) (U.S. or PCT) in the manner provided by the first paragraph of 35, U.S.C. '112, I acknowledge the duty to disclose information which is material to patentability as defined in 37 C.F.R. '1.56 which became available between the filing date of the prior application and the national or PCT International filing date of this application.

(List prior U.S. Applications or PCT International applications designating the U.S.)	(Application Serial No.)	(Filing Date)	(Status) (patented, pending, abandoned)
	(Application Serial No.)	(Filing Date)	(Status) (patented, pending, abandoned)

And I hereby appoint the firm of Arent Fox, Customer Number 004372 including as principal attorneys: Robert B. Murray, Reg. No. 22,980; Charles M. Marmelstein, Reg. No. 25,895; George E. Oram, Jr., Reg. No. 27,931; Douglas H. Goldhush, Reg. No. 33,125; David T. Nikaido, Reg. No. 22,663; Richard J. Berman, Reg. No. 39,107; King L. Wong, Reg. No. 37,500; James A. Poulos, III, Reg. No. 31,714; Murat Ozgu, Reg. No. 44,275; Robert K. Carpenter, Reg. No. 34,794; Gregory B. Kang, Reg. No. 45,273; Rustan Hill, Reg. No. 37,351; Carl Schaukowitch, Reg. No. 29,211; Kevin Turner, Reg. No. 43,437; Rhonda C. Barton, Reg. No. P47,271; Hans J. Crosby, Reg. No. 44,634; David D. Dzara, Reg. No. 47,543; Lynne D. Anderson, Reg. No. 46,412; David D. Dzara, Reg. No. 47,543; and Laurence J. Edson, Reg. No. 44,666.

Please direct all communications to the following address:

Customer No. 004372  
ARENT FOX KINTNER PLOTKIN & KAHN, PLLC  
1050 Connecticut Avenue, N.W., Suite 600  
Washington, D.C. 20036-5339  
Telephone No. (202) 857-6000; Facsimile No. (202) 638-4810

The undersigned hereby authorizes the U.S. attorneys named herein to accept and follow instructions from the undersigned's assignee, if any, and/or, if the undersigned is not a resident of the United States, the undersigned's domestic attorney, patent attorney or patent agent, as to any action to be taken in the Patent and Trademark Office regarding this application without direct communication between the U.S. attorneys and the undersigned. In the event of a change in the person(s) from whom instructions may be taken, the U.S. attorneys named herein will be so notified by the undersigned

I hereby declare that all statements made herein of my own knowledge are true and that all statements made on information and belief are believed to be true; and further, that these statements were made with the knowledge that willful false statements and the like so made are punishable by fine or imprisonment, or both, under Section 1001 of Title 18 of the United States Code and that such willful false statements may jeopardize the validity of the application or any patent issued thereon.

Full name of sole or first inventor Hiromu UESHIMA  
Inventor's signature [Signature] May 27, 2001  
Date

Residence Kusatsu-shi, Shiga, Japan  
Citizenship Japanese  
Post Office Address c/o SSD Company Limited, 3-3-4, Higashiyagura, Kusatsu-shi, Shiga 525-0054, Japan

Full name of sole or second inventor Katsuya NAKAGAWA  
Inventor's signature [Signature] May 27, 2001  
Date

Residence Kusatsu-shi, Shiga, Japan  
Citizenship Japanese  
Post Office Address c/o SSD Company Limited, 3-3-4, Higashiyagura, Kusatsu-shi, Shiga 525-0054, Japan

Full name of sole or third inventor \_\_\_\_\_  
Inventor's signature \_\_\_\_\_ Date \_\_\_\_\_

Residence \_\_\_\_\_  
Citizenship \_\_\_\_\_  
Post Office Address \_\_\_\_\_